



**Griffin-Spalding  
County Airport**  
Griffin, Georgia

**Michael Baker  
INTERNATIONAL**

Designer:  
**JCD, TGM**

Technician:  
**TGM**

Checked by:  
**JCD**

Project Number:  
**143849**

**NOTES**

- COORDINATES SHOWN ARE IN NAD83.
- ELEVATIONS SHOWN ARE IN NAVD88 AND ARE ABOVE MEAN SEA LEVEL (AMSL).
- OBSTRUCTION DATA SOURCE: PHOTO SCIENCE, FLOWN OCTOBER 22, 2014.
- BASED ON GENERAL PART 77 SURVEY FOR PLANNING PURPOSES ONLY. SURVEY BASE IS NOT A DETAILED OBSTRUCTION ANALYSIS COVERING ALL INDIVIDUAL OBSTRUCTIONS.
- REFER TO THE AIRPORT AIRSPACE DRAWING FOR FURTHER OUT OBSTRUCTIONS.
- FAA CLEARANCE REQUIREMENTS NOTE: SECTION 77.23 OF FEDERAL AVIATION REGULATIONS (FAR) PART 77 SPECIFIES CLEARANCE REQUIREMENTS FOR ROADS, RAILROADS, AND WATERWAYS AS FOLLOWS:
  - A. SEVENTEEN FEET FOR AN INTERSTATE HIGHWAY THAT IS PART OF THE NATIONAL SYSTEM OF MILITARY AND INTERSTATE HIGHWAYS WHERE OVERCROSSINGS ARE DESIGNED FOR A MINIMUM OF 17 FEET VERTICAL DISTANCE.
  - B. FIFTEEN FEET FOR ANY OTHER PUBLIC ROADWAY.
  - C. TEN FEET OR THE HEIGHT OF THE HIGHEST MOBILE OBJECT THAT WOULD NORMALLY TRAVERSE THE ROAD, WHICHEVER IS GREATER, FOR A PRIVATE ROAD.
  - D. TWENTY-THREE FEET FOR A RAILROAD, AND
  - E. FOR A WATERWAY OR ANY OTHER TRAVERSE WAY NOT PREVIOUSLY MENTIONED, AN AMOUNT EQUAL TO THE HEIGHT OF THE HIGHEST MOBILE OBJECT THAT WOULD NORMALLY TRAVERSE IT.

**REVISIONS**

No.	Description	Date	By

Project Name:  
**AIRPORT  
LAYOUT  
PLAN**

Drawing Name:  
**OBSTRUCTION  
DATA SHEET -  
RUNWAY 30  
DEPARTURE SURFACE**

AIP Project Number:

Autocad Drawing Reference:

Date: **JULY 2017** Division: **PLANNING**

Scale: **HORIZONTAL: 1" = 1,000'**  
**VERTICAL: 1" = 100'** Drawing Number: **16**

**INTERIM / ULTIMATE DEPARTURE SURFACE OBSTRUCTION TABLE - RUNWAY 30**

OBST. NO.	OBST. TYPE	TOP OF OBJ. ELEV.	SURFACE PENETR.	PROPOSED ACTION	OBST. NO.	OBST. TYPE	TOP OF OBJ. ELEV.	SURFACE PENETR.	PROPOSED ACTION
2	TREE	976.1'	12.3'	TRIM / REMOVE	541	TREE	919.0'	19.5'	TRIM / REMOVE
3	TREE	962.8'	2.7'	TRIM / REMOVE	546	TREE	934.5'	4.1'	TRIM / REMOVE
6	TREE	964.3'	2.5'	TRIM / REMOVE	550	TREE	909.1'	9.3'	TRIM / REMOVE
31	TREE	953.8'	4.5'	TRIM / REMOVE	552	TREE	930.6'	33.6'	TRIM / REMOVE
32	TREE	956.2'	4.4'	TRIM / REMOVE	554	TREE	947.2'	15.0'	TRIM / REMOVE
35	TREE	951.0'	3.1'	TRIM / REMOVE	556	TREE	946.0'	17.7'	TRIM / REMOVE
40	TREE	958.7'	9.3'	TRIM / REMOVE	558	TREE	934.2'	3.6'	TRIM / REMOVE
44	TREE	963.1'	15.6'	TRIM / REMOVE	563	TREE	935.2'	38.7'	TRIM / REMOVE
46	TREE	949.5'	0.1'	TRIM / REMOVE	567	TREE	914.4'	19.3'	TRIM / REMOVE
49	TREE	959.8'	12.1'	TRIM / REMOVE	571	TREE	949.2'	21.7'	TRIM / REMOVE
52	TREE	958.9'	9.5'	TRIM / REMOVE	572	TREE	923.3'	8.7'	TRIM / REMOVE
59	TREE	944.5'	0.3'	TRIM / REMOVE	574	TREE	910.6'	13.9'	TRIM / REMOVE
62	TREE	947.2'	0.2'	TRIM / REMOVE	575	TREE	920.8'	25.8'	TRIM / REMOVE
64	TREE	953.0'	7.4'	TRIM / REMOVE	577	TREE	931.5'	3.0'	TRIM / REMOVE
72	TREE	952.1'	6.6'	TRIM / REMOVE	580	TREE	928.0'	14.8'	TRIM / REMOVE
79	TREE	959.4'	17.8'	TRIM / REMOVE	582	TREE	932.5'	8.2'	TRIM / REMOVE
85	TREE	949.6'	7.1'	TRIM / REMOVE	583	TREE	897.8'	3.9'	TRIM / REMOVE
87	TREE	967.6'	27.5'	TRIM / REMOVE	585	TREE	954.9'	29.8'	TRIM / REMOVE
90	TREE	960.4'	17.4'	TRIM / REMOVE	592	TREE	917.1'	25.6'	TRIM / REMOVE
95	TREE	945.2'	1.0'	TRIM / REMOVE	593	TREE	898.8'	4.9'	TRIM / REMOVE
96	TREE	961.9'	22.1'	TRIM / REMOVE	596	TREE	942.1'	19.9'	TRIM / REMOVE
99	TREE	960.9'	20.2'	TRIM / REMOVE	599	TREE	942.8'	19.4'	TRIM / REMOVE
100	TREE	955.0'	13.2'	TRIM / REMOVE	600	TREE	907.4'	16.1'	TRIM / REMOVE
108	TREE	952.8'	15.4'	TRIM / REMOVE	605	TREE	922.2'	9.6'	TRIM / REMOVE
109	TREE	949.9'	7.9'	TRIM / REMOVE	606	TREE	941.1'	21.1'	TRIM / REMOVE
112	TREE	954.7'	16.3'	TRIM / REMOVE	608	TREE	907.4'	15.7'	TRIM / REMOVE
121	TREE	966.3'	3.5'	TRIM / REMOVE	610	TREE	913.8'	23.7'	TRIM / REMOVE
261	TREE	935.0'	12.1'	TRIM / REMOVE	611	TREE	919.5'	1.2'	TRIM / REMOVE
262	TREE	925.8'	1.2'	TRIM / REMOVE	612	TREE	898.3'	6.0'	TRIM / REMOVE
268	TREE	935.1'	11.7'	TRIM / REMOVE	613	TREE	908.1'	18.0'	TRIM / REMOVE
271	TREE	942.0'	20.3'	TRIM / REMOVE	615	TREE	932.8'	10.9'	TRIM / REMOVE
278	TREE	928.0'	3.6'	TRIM / REMOVE	617	TREE	936.9'	17.5'	TRIM / REMOVE
279	TREE	928.4'	5.0'	TRIM / REMOVE	621	TREE	921.2'	11.2'	TRIM / REMOVE
283	TREE	933.9'	1.3'	TRIM / REMOVE	622	TREE	927.4'	15.3'	TRIM / REMOVE
289	TREE	922.0'	1.9'	TRIM / REMOVE	628	TREE	905.5'	2.2'	TRIM / REMOVE
298	TREE	931.9'	0.3'	TRIM / REMOVE	629	TREE	910.3'	22.1'	TRIM / REMOVE
302	TREE	924.2'	4.1'	TRIM / REMOVE	632	TREE	928.8'	16.8'	TRIM / REMOVE
305	TREE	929.5'	5.7'	TRIM / REMOVE	633	TREE	934.2'	26.1'	TRIM / REMOVE
315	TREE	945.9'	0.8'	TRIM / REMOVE	634	TREE	900.3'	10.4'	TRIM / REMOVE
316	TREE	924.1'	2.0'	TRIM / REMOVE	635	TREE	925.9'	16.0'	TRIM / REMOVE
327	TREE	927.6'	2.5'	TRIM / REMOVE	636	TREE	904.9'	16.9'	TRIM / REMOVE
350	TREE	932.4'	5.2'	TRIM / REMOVE	637	TREE	918.3'	5.6'	TRIM / REMOVE
351	TREE	928.6'	4.0'	TRIM / REMOVE	638	TREE	934.0'	15.5'	TRIM / REMOVE
363	TREE	927.6'	2.7'	TRIM / REMOVE	640	TREE	919.3'	5.2'	TRIM / REMOVE
364	TREE	925.2'	3.8'	TRIM / REMOVE	641	TREE	941.9'	24.9'	TRIM / REMOVE
369	TREE	932.6'	6.7'	TRIM / REMOVE	642	TREE	934.2'	23.6'	TRIM / REMOVE
382	TREE	925.5'	4.3'	TRIM / REMOVE	647	TREE	917.8'	3.5'	TRIM / REMOVE
385	TREE	920.3'	9.9'	TRIM / REMOVE	649	TREE	931.1'	24.2'	TRIM / REMOVE
406	TREE	923.4'	5.4'	TRIM / REMOVE	651	TREE	928.6'	18.4'	TRIM / REMOVE
411	TREE	918.3'	7.6'	TRIM / REMOVE	652	TREE	923.2'	11.5'	TRIM / REMOVE
422	TREE	938.2'	1.9'	TRIM / REMOVE	654	TREE	923.9'	19.5'	TRIM / REMOVE
427	TREE	926.6'	18.0'	TRIM / REMOVE	656	TREE	926.2'	18.5'	TRIM / REMOVE
429	TREE	942.8'	5.3'	TRIM / REMOVE	658	TREE	930.6'	22.0'	TRIM / REMOVE
433	TREE	917.2'	10.3'	TRIM / REMOVE	659	TREE	919.0'	3.7'	TRIM / REMOVE
448	TREE	917.3'	11.1'	TRIM / REMOVE	660	TREE	928.6'	18.4'	TRIM / REMOVE
452	TREE	921.9'	13.0'	TRIM / REMOVE	661	TREE	891.2'	4.8'	TRIM / REMOVE
455	TREE	920.0'	13.0'	TRIM / REMOVE	665	TREE	923.5'	18.9'	TRIM / REMOVE
460	TREE	941.4'	6.9'	TRIM / REMOVE	666	TREE	917.1'	6.0'	TRIM / REMOVE
469	TREE	929.2'	1.9'	TRIM / REMOVE	667	TREE	902.1'	18.1'	TRIM / REMOVE
472	TREE	920.3'	0.1'	TRIM / REMOVE	670	TREE	928.8'	26.5'	TRIM / REMOVE
476	TREE	939.4'	4.7'	TRIM / REMOVE	672	TREE	886.0'	1.5'	TRIM / REMOVE
477	TREE	923.6'	19.8'	TRIM / REMOVE	677	TREE	909.7'	2.9'	TRIM / REMOVE
479	TREE	913.4'	6.6'	TRIM / REMOVE	678	TREE	903.9'	20.6'	TRIM / REMOVE
485	TREE	936.7'	0.5'	TRIM / REMOVE	680	TREE	920.3'	8.3'	TRIM / REMOVE
487	TREE	913.5'	1.2'	TRIM / REMOVE	685	TREE	897.7'	15.6'	TRIM / REMOVE
492	TREE	919.8'	16.1'	TRIM / REMOVE	686	TREE	909.7'	2.8'	TRIM / REMOVE
497	TREE	935.6'	13.8'	TRIM / REMOVE	690	TREE	884.3'	0.4'	TRIM / REMOVE
498	TREE	948.5'	16.1'	TRIM / REMOVE	694	TREE	913.9'	11.9'	TRIM / REMOVE
501	TREE	935.2'	1.0'	TRIM / REMOVE	697	TREE	907.0'	2.5'	TRIM / REMOVE
503	TREE	922.6'	21.0'	TRIM / REMOVE	700	TREE	901.5'	19.4'	TRIM / REMOVE
505	TREE	941.6'	5.2'	TRIM / REMOVE	702	TREE	917.8'	8.1'	TRIM / REMOVE
506	TREE	914.1'	1.4'	TRIM / REMOVE	707	TREE	909.8'	30.2'	TRIM / REMOVE
509	TREE	917.2'	13.3'	TRIM / REMOVE	708	TREE	920.5'	12.1'	TRIM / REMOVE
512	TREE	933.3'	13.0'	TRIM / REMOVE	711	TREE	903.1'	0.8'	TRIM / REMOVE
519	TREE	920.6'	19.2'	TRIM / REMOVE	712	TREE	915.6'	8.6'	TRIM / REMOVE
521	TREE	921.9'	19.8'	TRIM / REMOVE	714	TREE	895.7'	15.6'	TRIM / REMOVE
523	TREE	920.5'	1.1'	TRIM / REMOVE	715	TREE	908.1'	28.7'	TRIM / REMOVE
524	TREE	941.4'	7.5'	TRIM / REMOVE	719	TREE	898.2'	1.0'	TRIM / REMOVE
528	TREE	949.5'	17.7'	TRIM / REMOVE	729	TREE	917.8'	41.0'	TRIM / REMOVE
529	TREE	919.5'	8.2'	TRIM / REMOVE	731	TREE	899.8'	22.5'	TRIM / REMOVE
530	TREE	925.0'	22.5'	TRIM / REMOVE	744	TREE	916.3'	41.1'	TRIM / REMOVE
537	TREE	939.9'	10.1'	TRIM / REMOVE	793	TREE	894.5'	6.4'	TRIM / REMOVE
539	TREE	942.6'	10.6'	TRIM / REMOVE					

**INTERIM / ULTIMATE RUNWAY 30 TRAVERSE WAY TABLE**

OBSTRUCTION NO.	ROADWAY ELEVATION	+ PART 77.23 STANDARDS	SURFACE PENETRATION	PROPOSED ACTION
RD1	804.2'	819.2'	-57.3'	NO ACTION
RD2	824.2'	839.2'	-60.8'	NO ACTION
RD3	828.1'	843.1'	-68.3'	NO ACTION
RD4	824.3'	839.3'	-76.6'	NO ACTION
RD5	866.1'	881.1'	-64.0'	NO ACTION